BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Name of Work:- Construction of Hospital building at ward no 11 Kuvempunagara in Vidyaranypura Sub Division

SNo	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the exavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	674.86	329.00	Rupees Three Hundred Twenty Nine Only
2	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	44.05	2456.00	Rupees Two Thousand Four Hundred Fifty Six Only
3	Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	67.51	5676.00	Rupees Five Thousand Six Hundred Seventy Six Only
4	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	151.54	6345.00	Rupees Six Thousand Three Hundred Forty Five Only
5	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerddressed in courses not less than 20 cms high, bond stones at 2m apart in each course including cost of materials, labour, curing completeas per specifications and as per the directions of the Engineer-in-charge of the work ---- All terms and conditions are as per Tender Document	Cum	17.50	4882.00	Rupees Four Thousand Eight Hundred Eighty Two Only
6	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	198.94	148.00	Rupees One Hundred Forty Eight Only
7	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Sqm	427.32	269.00	Rupees Two Hundred Sixty Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications and as per the directions of the Engineer-in-charge of the work. --- All terms and conditions are as per Tender Document	Sqm	95.73	342.00	Rupees Three Hundred Forty Two Only
	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work (GROUND & BASEMENT FLOOR) --- All terms and conditions are as per Tender Document	Sqm	359.07	426.00	Rupees Four Hundred Twenty Six Only
10	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	185.79	432.00	Rupees Four Hundred Thirty Two Only
11	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	185.79	438.00	Rupees Four Hundred Thirty Eight Only
12	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work (HEADROOM ---- All terms and conditions are as per Tender Document	Sqm	33.60	443.00	Rupees Four Hundred Forty Three Only
13	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	1598.67	365.00	Rupees Three Hundred Sixty Five Only
14	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	620.43	370.00	Rupees Three Hundred Seventy Only
15	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	620.43	375.00	Rupees Three Hundred Seventy Five Only
16	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	34.16	382.00	Rupees Three Hundred Eighty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
17	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	36.32	790.00	Rupees Seven Hundred Ninety Only
18	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	16.34	795.00	Rupees Seven Hundred Ninety Five Only
19	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	16.34	802.00	Rupees Eight Hundred Two Only
20	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floors including cost of all materials,labour complete as per specifications and as per the directions of the Engineer-in-charge of the work . (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	3.51	807.00	Rupees Eight Hundred Seven Only
21	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons and as per the directions of the Engineer-in-charge of the work (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	958.51	298.00	Rupees Two Hundred Ninety Eight Only
22	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	500.82	303.00	Rupees Three Hundred Three Only
23	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	500.46	309.00	Rupees Three Hundred Nine Only
24	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons and as per the directions of the Engineer-in-charge of the work (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	29.04	315.00	Rupees Three Hundred Fifteen Only
25	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	142.92	554.00	Rupees Five Hundred Fifty Four Only
26	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	30.57	559.00	Rupees Five Hundred Fifty Nine Only

Contractor

Executive Engine
Project D
Yelahanka Zon

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
27	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	30.57	564.00	Rupees Five Hundred Sixty Four Only
28	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	24.60	315.00	Rupees Three Hundred Fifteen Only
29	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	34.50	320.00	Rupees Three Hundred Twenty Only
30	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	30.36	326.00	Rupees Three Hundred Twenty Six Only
31	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour complete as per specificaiton and as per the directions of the Engineer-in-charge of the work . (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	0.96	332.00	Rupees Three Hundred Thirty Two Only
32	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and First Floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	156.22	7255.00	Rupees Seven Thousand Two Hundred Fifty Five Only
33	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in Ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars, posts, struts. butters, string or lacing courses , parapets, coping, bed blocks, anchor blocks ,plain window cills, fillets including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.ets including cost of all materials, labour,HOM of machinery, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Cum	55.98	7426.00	Rupees Seven Thousand Four Hundred Twenty Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in First Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars, posts, struts. butters, string or lacing courses , parapets, coping, bed blocks, anchor blocks ,plain window cills, fillets including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.ets including cost of all materials, labour,HOM of machinery, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Cum	32.19	7485.00	Rupees Seven Thousand Four Hundred Eighty Five Only
35	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in Ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars, posts, struts. butters, string or lacing courses , parapets, coping, bed blocks, anchor blocks ,plain window cills, fillets including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.ets including cost of all materials, labour,HOM of machinery, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Cum	32.20	7542.00	Rupees Seven Thousand Five Hundred Forty Two Only
36	Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum andfine aggregtes @ 0.47cum,with superplastisiser @3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick,vibrated fo all works in Ground Floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thivck ness) including attached plasters ,columns, pillars, posts, struts. butters, string or lacing courses , parapets, coping, bed blocks, anchor blocks ,plain window cills, fillets including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.ets including cost of all materials, labour,HOM of machinery, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (HEADROOM) ---- All terms and conditions are as per Tender Document	Cum	3.26	7600.00	Rupees Seven Thousand Six "Hundred Only
37	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar,with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed cement for concrete for beams,staircase,and roof with M-25 and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	726.27	7075.00	Rupees Seven Thousand Seventy Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
38	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	19.23	599.00	Rupees Five Hundred Ninety Nine Only
39	KSRB 4.2.11 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	27.00	605.00	Rupees Six Hundred Five Only
40	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	23.76	610.00	Rupees Six Hundred Ten Only
41	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto First Floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	0.72	616.00	Rupees Six Hundred Sixteen Only
42	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Tonne	75.00	56950.00	Rupees Fifty Six Thousand Nine Hundred Fifty Only
43	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Tonne	26.77	57500.00	Rupees Fifty Seven Thousand Five Hundred Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
44	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Tonne	26.73	58218.00	Rupees Fifty Eight Thousand Two Hundred Eighteen Only
45	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per the directions of the Engineer-in-charge of the work . (HEADROOM) ---- All terms and conditions are as per Tender Document	Tonne	1.90	58600.00	Rupees Fifty Eight Thousand Six Hundred Only
46	Providing and constructing load bearing wall with precast solid concrete blocks of size 400X400X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	711.51	1092.00	Rupees One Thousand Ninety Two Only
47	Providing and constructing load bearing wall with precast solid concrete blocks of size 400X400X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	274.41	1127.00	Rupees One Thousand One Hundred Twenty Seven Only
48	Providing and constructing load bearing wall with precast solid concrete blocks of size 400X400X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	352.37	1162.00	Rupees One Thousand One Hundred Sixty Two Only
49	Providing and constructing load bearing wall with precast solid concrete blocks of size 400X400X200mm having block density not less than 1800kg/m3 having a minimum average compressive strength 5.00N/mm2 confirming to IS 2185 (part 1) :2005 and constructed with cement mortar 1:4,as per IS 2572:2005 including cost of materials, labour charges, scaffolding, curing, hire charges of machinaries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	29.76	1197.00	Rupees One Thousand One Hundred Ninety Seven Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
50	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	158.65	835.00	Rupees Eight Hundred Thirty Five Only
51	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	123.78	869.00	Rupees Eight Hundred Sixty Nine Only
52	Providing and constructing non-load bearing wall with solid concrete blocks of size 400X100X200 having a block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 conforming to I.S : 2185 (Part 1) : 2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials, labour charges, scaffolding, curing, hire chargesof machineries etc., complete as per specifications and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	82.65	905.00	Rupees Nine Hundred Five Only
53	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	394.11	257.00	Rupees Two Hundred Fifty Seven Only
54	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	383.15	268.00	Rupees Two Hundred Sixty Eight Only
55	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	565.65	280.00	Rupees Two Hundred Eighty Only
56	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners. wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	68.91	292.00	Rupees Two Hundred Ninety Two Only
57	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	1650.56	192.00	Rupees One Hundred Ninety Two Only

Contractor

Executive Engin
Project D
Yelahanka Zo

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
58	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	754.13	197.00	Rupees One Hundred Ninety Seven Only
59	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	809.87	204.00	Rupees Two Hundred Four Only
60	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	107.37	209.00	Rupees Two Hundred Nine Only
61	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specification and as per the directions of the Engineer-in-charge of the work (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	119.37	206.00	Rupees Two Hundred Six Only
62	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specification and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	32.22	212.00	Rupees Two Hundred Twelve Only
63	Providing rough cement plastering 15mm thick in single coat with cement mortar 1:4 to brick masonry for base of dadooing works with sand of approved quality, providing and removing scaffolding, inclding cost of materials, labour, curing complete as per specification and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	24.51	217.00	Rupees Two Hundred Seventeen Only
64	Providing 12mm thick cement plaster in single coat with cement mortar 1:4 , to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Sqm	4129.37	207.00	Rupees Two Hundred Seven Only
65	providing applying two coats of wall putty to inside plastered walls and ceiling using white cement putty . Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of alll mateerial cost of labour and scaffolding etc. ,complete as per specification and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Sqm	8863.12	65.00	Rupees Sixty Five Only

Contractor

Executive Engi
Project D
Yelahanka Zo

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
66	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work ---- All terms and conditions are as per Tender Document	Sqm	3321.93	82.00	Rupees Eighty Two Only
67	Extra over Above for applying oil bound washable distemper on ceiling and / or sloping roof as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Sqm	4038.95	89.00	Rupees Eighty Nine Only
68	Providing and finishing external walls in two coats with waterproof cement paint of approved brand with primer and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	418.71	97.00	Rupees Ninety Seven Only
69	Providing and finishing external walls in two coats with waterproof cement paint of approved brand with primer and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	417.65	105.00	Rupees One Hundred Five Only
70	Providing and finishing external walls in two coats with waterproof cement paint of approved brand with primer and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	596.01	111.00	Rupees One Hundred Eleven Only
71	Providing and finishing external walls in two coats with waterproof cement paint of approved brand with primer and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work (HEADROOM) ---- All terms and conditions are as per Tender Document	Sqm	69.87	119.00	Rupees One Hundred Nineteen Only
72	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, curing etc.,complete and as per the directions of the Engineer-in-charge of the work . (GROUND & BASEMENT FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	40.05	4650.00	Rupees Four Thousand Six Hundred Fifty Only
73	Providing and laying Hassan Green granite flooring for staircase, treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, curing etc.,complete and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	22.05	4652.00	Rupees Four Thousand Six Hundred Fifty Two Only

Contractor

Executive Engine
Project Divisi
Yelahanka Zon

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
	Providing and laying Hassan Green granite flooring for staircase, landings and risers using pre polished 20 mm thick water cut green granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing , cutting 3 line grooves not more than 2 mm wide for antiskidding, curing etc complete and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	22.05	4653.00	Rupees Four Thousand Six Hundred Fifty Three Only
75	Providing and fixing Vetrified glazed tiles of approved make quality & colour of size 600x 600x 10 mm thick fixed on existing flooring withspecial adhesive for flooring ,skirting ad jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc complete as per specification and as per the directions of the Engineer-in-charge of the work (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	483.65	1246.00	Rupees One Thousand Two Hundred Forty Six Only
76	Providing and fixing Vetrified glazed tiles of approved make quality & colour of size 600x 600x 10 mm thick fixed on existing flooring withspecial adhesive for flooring ,skirting ad jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc complete as per specification and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	589.00	1248.00	Rupees One Thousand Two Hundred Forty Eight Only
77	Providing and fixing Vetrified glazed tiles of approved make quality & colour of size 600x 600x 10 mm thick fixed on existing flooring withspecial adhesive for flooring ,skirting ad jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc complete as per specification and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	623.05	1250.00	Rupees One Thousand Two Hundred Fifty Only
78	Providing and fixing Vetrified glazed tiles of approved make quality & colour of size 600x 600x 10 mm thick fixed on existing flooring withspecial adhesive for flooring ,skirting ad jointed with neat cement slurry mixed with pigment to match shade of tiles, including providing spacers at required interval and removing stains etc complete as per specification and as per the directions of the Engineer-in-charge of the work (HEADOOM) ---- All terms and conditions are as per Tender Document	Sqm	9.36	1251.00	Rupees One Thousand Two Hundred Fifty One Only
79	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	23.54	1371.00	Rupees One Thousand Three Hundred Seventy One Only
80	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. and as per the directions of the Engineer-in-charge of the work (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	5.76	1373.00	Rupees One Thousand Three Hundred Seventy Three Only
81	Providing Ceramic tiles of size 30x30cms 6mm thick of approved make ,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications. and as per the directions of the Engineer-in-charge of the work (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	5.78	1375.00	Rupees One Thousand Three Hundred Seventy Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
82	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	118.82	1730.00	Rupees One Thousand Seven Hundred Thirty Only
83	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	37.59	1733.00	Rupees One Thousand Seven Hundred Thirty Three Only
84	Providing skirting, dado, rises of steps with colour glazed tiles 30X60 cms 6mm thick with border of size 30 x 10 cms on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work . (SECOND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	42.38	1735.00	Rupees One Thousand Seven Hundred Thirty Five Only
85	Fixing of door frames in an existing opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Nos	46.00	1229.00	Rupees One Thousand Two Hundred Twenty Nine Only
86	Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries complete as per specifications and as per the directions of the Engineer-in-charge of the work . ---- All terms and conditions are as per Tender Document	Cum	3.68	#########	Rupees One Lakh(s) Nineteen Thousand Nine Hundred Seventy Only
87	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) (GROUND FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	37.80	5415.00	Rupees Five Thousand Four Hundred Fifteen Only
88	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) (FIRST FLOOR) ---- All terms and conditions are as per Tender Document	Sqm	11.34	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Contractor

Executive Engine
Project Divi
Yelahanka Zo